



IFPRI®

FCNDP No. 158

FCND DISCUSSION PAPER NO. 158

FOOD AID AND CHILD NUTRITION IN RURAL ETHIOPIA

Agnes R. Quisumbing

Food Consumption and Nutrition Division

International Food Policy Research Institute

2033 K Street, N.W.

Washington, D.C. 20006 U.S.A.

(202) 862-5600

Fax: (202) 467-4439

September 2003

Copyright © 2003 International Food Policy Research Institute

FCND Discussion Papers contain preliminary material and research results, and are circulated prior to a full peer review in order to stimulate discussion and critical comment. It is expected that most Discussion Papers will eventually be published in some other form, and that their content may also be revised.

Abstract

This paper uses a unique panel data set from Ethiopia to examine the determinants of participation in and receipts of food aid through free distribution (FD) and food-for-work (FFW). Results show that aggregate rainfall and livestock shocks increase household participation in both FD and FFW. FFW also seems well-targeted to asset-poor households. The probability of receiving FD does not appear to be targeted based on household wealth, but FD receipts are lower for wealthier households. The effects of FD and FFW on child nutritional status differ depending on the modality of food aid and the gender of the child. Both FFW and FD have a positive direct impact on weight-for-height. Households invest proceeds from FD in girls' nutrition, while earnings from FFW are manifested in better nutrition for boys. The effects of the gender of the aid recipient are not conclusive.

Keywords: food aid, child nutrition, Ethiopia

Contents

Acknowledgments.....	v
1. Introduction.....	1
2. Conceptual Model.....	4
3. Data.....	7
4. Empirical Specification.....	12
Determinants of FFW and FD receipts.....	12
Determinants of Child Nutritional Status.....	14
5. Results.....	15
Determinants of Participation in and Receipts from Food-for-Work and Food Aid Programs.....	15
Impact of Food-for-Work and Food Aid on Child Nutritional Status.....	18
6. Conclusions and Policy Implications.....	23
References.....	26

Tables

1	Characteristics of sample households, by survey round, Ethiopia Rural Household Survey	10
2	Trends in wasting and stunting, by survey round	11
3	Weight-for-height and height-for-age Z scores, by sex	11
4	Determinants of days worked and payments received, food-for-work program, Heckman maximum likelihood estimates	16
5	Determinants of food distribution receipts, Heckman maximum likelihood estimates	19
6	Effects of FD and FFW on child weight-for-height and height-for-age, low-asset households	20
7	Effects of FD and FFW on child weight-for-height and height-for-age, high-asset households	21

Figure

1	Ethiopian Rural Household Survey (ERHS) sites	8
---	---	---

Acknowledgments

This paper was prepared for the conference on Crises and Disasters: Measurement and Mitigation of their Human Costs, sponsored by the Inter-American Development Bank (IDB) and the International Food Policy Research Institute (IFPRI), Washington, D.C., November 13–14, 2001. Funding for collection of the fourth round of panel data came from Grant No. FAO-0100-G-00-5020-00, on Strengthening Development Policy Through Gender Analysis: An Integrated Multicountry Research Program, from the U.S. Agency for International Development’s Office of Women in Development. I am grateful to Addis Ababa University and the Centre for the Study of African Economies, Oxford, for access to the earlier rounds of the Ethiopia Rural Household Survey. I thank Stuart Gillespie, Markus Goldstein, Robin Jackson, Marie Ruel, Emmanuel Skoufias, Lisa Smith, Takashi Yamano, and seminar participants at the IDB and IFPRI for helpful comments and suggestions, and Lourdes Hinayon for help in finalizing the document. The usual disclaimers apply.

Agnes R. Quisumbing
International Food Policy Research Institute

1. Introduction

Food aid programs have become increasingly important for disaster relief in many developing countries. In Ethiopia, a drought-stricken economy with one of the lowest per capita incomes in the world, food aid has amounted to almost 10 million metric tons (mt) from 1984 to 1998, almost 10 percent of annual cereal production (Jayne et al. 2002). Because of the importance of food aid in Ethiopia, much effort has been devoted to evaluation of its effectiveness (Clay, Molla, and Habtewold 1999; Barrett and Clay 2001). Discussions have often focused on the appropriate modality of food aid, whether free distribution (FD) or food-for-work (FFW), the two historically important forms of food aid in Ethiopia (Webb, von Braun, and Yohannes 1992). Ethiopia's official food aid policy states that no able-bodied person should receive food aid without working on a community project in return, supplemented by targeted free food aid for those who cannot work. FD programs distribute cereals (wheat, maize, and sorghum) directly to households, while participants in FFW programs typically work in community development programs, such as roads, terraces, dams, and local infrastructure construction. The government of Ethiopia now devotes 80 percent of its food assistance resources to FFW programs, using the principle of self-targeting (Ethiopia 1996). While much of the literature on FFW has found that self-targeting employment schemes are effective in reaching the poor, recent evaluations in Ethiopia have found alternative explanations for the targeting of food aid—among which bureaucratic inertia or a history of past receipts of food aid is one of the most important determinants (Jayne et al. 2002).

Many evaluations of food aid have examined its impact on household calorie availability. This paper focuses on the effects of food aid on *individual* nutritional status, as measured by indicators of child nutrition. The few existing studies of the effects of food aid on individual nutritional status do not conclusively indicate whether participation in public works improved nutritional status nor measure its long-term impact. For example, Webb and Kumar (1995), using data from a public works program in Niger, found that children in high-participation households tended to be more

malnourished than those from low-participation households. However, this could be due to the successful targeting of FFW rather than its impact. Brown, Yohannes, and Webb (1994), using the same data, find that the female shares of public works receipts and days worked in FFW have greater positive impacts on child weight-for-age Z scores, controlling for the endogeneity of household calorie availability and days worked by males and females in FFW. However, since the data come from a single cross-section, analysis of the longer-term impact of FFW was not possible. Moreover, weight-for-age Z-scores capture both long- and short-term effects, making it difficult to infer causality from public works participation during the previous year to current nutritional status.

This paper takes a slightly different perspective from the above studies in evaluating the impact of food aid. First, it draws on a growing body of empirical literature that rejects the unitary model of the household in a variety of settings.¹ If, as this literature suggests, individuals within households have different preferences and do not pool their resources, the effect of public transfers such as food aid may differ, depending on who the recipient is. Indeed, recent human capital investment programs, such as the *Programa Nacional de Educacion, Salud y Alimentacion (PROGRESA)* in Mexico, have deliberately targeted cash transfers to women on the grounds that resources controlled by women are associated with better educational and nutritional outcomes of children (Skoufias 2003). Moreover, the World Food Programme (WFP)—through which one-quarter to one-third of global food aid has been channeled since the late 1980s and which is the major food aid donor in Ethiopia—has recently announced that it will require women to control the family entitlement in 80 percent of the operations it handles directly or subcontracts (Barrett 2002; World Food Programme 1996). Drawing from this literature, the paper examines whether the impact on nutritional status differs, depending on the gender of the aid recipient and the gender of the child.

¹ For reviews, see Strauss and Thomas (1995), Behrman (1997), and Haddad, Hoddinott, and Alderman (1997).

Second, in line with debates on the appropriate modality of food aid, the paper investigates the determinants of participation in, and receipts of, food aid through FD or FFW, and whether the two modalities of food aid delivery represented by these programs matter for the impacts on nutritional status. The distinction is not between the form of the transfer (cash versus food), but the possibility that FD and FFW have different effects on the household's budget constraint, which, in turn, may affect the transfer's impact.² For example, in Ethiopia, Yamano (2000) finds that FD tends to increase farm labor supply of girls, while FFW decreases it. Lastly, this paper is able to take into account the possible endogeneity and codetermination of nutritional status and food aid by making use of a unique panel data set from rural Ethiopia that contains information on individual anthropometric outcomes and household food aid receipts for four survey rounds between 1994 and 1997.³ Since there are multiple observations on individuals, the paper is also able to ascertain whether there are longer-term effects of food aid on nutritional status.

Results show that aggregate rainfall and livestock shocks increase household participation in both FD and FFW. FFW also seems well-targeted to asset-poor households, but the probability of receiving FD does not appear to be affected by household wealth. Conditional on being included in FD, however, FD receipts decline for wealthier households. The effects of FD and FFW on child nutritional status differ depending on the modality of food aid and the gender of the child. Both FFW and FD have a positive direct impact on weight-for-height, which responds more quickly to short-run interventions than does height-for-age. Households seem to invest proceeds from FD (which can be interpreted as an increase in unearned income) in girls' nutrition, while earnings from FFW are manifested in better nutrition for boys. The effects of the gender of the aid recipient are inconclusive.

² There is a separate literature on the desirability of cash versus food in income transfer programs. See, for example, Barrett (2002) and Rogers (1988).

³ The data set is described more fully in Dercon and Krishnan (2000a, 2000b) and Fafchamps and Quisumbing (2002).

The rest of the paper is organized as follows. Section 2 presents a brief conceptual model of child nutrition. Section 3 describes the survey and presents descriptive statistics. Section 4 discusses the empirical specification, while Section 5 presents the results on the determinants of FD and FFW and their impact on child nutritional status. Section 6 concludes and discusses policy implications from the research.

2. Conceptual Model

A simple model can be used to illustrate the differential effects of FD and FFW on child nutrition. Suppose that the household utility function can be characterized as:

$$U = U(X_p, X_h, L), \quad (1)$$

where X_p refers to market-purchased goods, X_h refers to home-produced goods, such as child health and nutrition, and L is leisure. At this point the assumption is that the household has a single utility function, although this assumption is later relaxed. The simplifying assumption is made that home-produced goods depend only on household labor supply, t_h .⁴ That is,

$$X_h = f(t_h). \quad (2)$$

Suppose the household derives income from agricultural production, wage labor, and participation in FFW activities. Suppose also that the household may be eligible to receive food aid through free distribution. Since free distribution does not require work, it is treated as unearned income.⁵

The household income constraint can then be written as

$$p_a \cdot Q_a(A, t_a) + w \cdot t_w + w_f \cdot t_f + N = pX_p, \quad (3)$$

⁴ This is similar to the exposition in Strauss and Thomas (1995).

⁵ This abstracts from the time costs of obtaining food aid through free distribution.

where $p_a \cdot Q_a$ is the value of agricultural output, which is a function of land and other agricultural assets A and of time allocated to agricultural production t_a . $w \cdot t_w$ is income from wage labor, where w is the market wage rate, and t_w is time spent in the labor market. w_f is the wage rate offered in FFW, which may be lower than the market wage rate for self-targeting purposes. Finally, N is unearned income, which may include transfers such as those from FD. Household income is spent on purchases of the market-produced good, X_p .

The time of individuals in the household is allocated to time in own agricultural production, time spent in the wage labor market, time on FFW activities, time producing home goods, and leisure. Thus, the household time constraint is as follows:

$$T = t_a + t_w + t_f + t_h + L. \quad (4)$$

Incorporating the household time constraint into the income constraint, the full income constraint can be written as

$$pX_p + w \cdot L = wT + (p_a \cdot Q_a - w t_a) + (p_h X_h - w t_h) + N. \quad (5)$$

That is, total consumption, including the value of time spent in leisure, cannot exceed full income. Full income is the value of time available to all household members, returns from agricultural production, “profits” from home production, and nonlabor income N . Maximizing equation (1) subject to the full income constraint yields reduced form demand functions for goods \mathbf{x} and leisure L , which can be written as a function of prices, the vector of wages \mathbf{w} (which includes both market wages and wages in FFW), and unearned income N , given the household’s asset levels:

$$\mathbf{x} = \mathbf{x}(\mathbf{p}, \mathbf{w}, N; A), \quad (6)$$

$$L = l(\mathbf{p}, \mathbf{w}, N; A). \quad (7)$$

Suppose, however, that the household is composed of two individuals, m and f (male and female), who do not have the same preferences, nor pool their incomes. A

collective model of the household would then be more appropriate, and the demand functions would be⁶

$$x_i = x_i(\mathbf{p}, \mathbf{w}, N_m, N_f, A_m, A_f, \alpha_m, \alpha_f); \quad i = 0, m, f. \quad (8)$$

$$L_i = L_i(\mathbf{p}, \mathbf{w}, N_m, N_f, A_m, A_f, \alpha_m, \alpha_f); \quad i = m, f. \quad (9)$$

In addition to wages and prices, the demand functions are conditioned on individual assets A_m and A_f and extrahousehold environmental parameters (EEPs) α_m and α_f . The EEPs affect the relative desirability of being outside the household (e.g., being single) and may include access to common property resources and divorce laws. Gender-specific targeting practiced in many FFW programs could also be viewed as an EEP that increases women's options outside marriage. Moreover, if spouses do not pool incomes, lump sum transfers such as free food distribution could have different effects, depending on whether the husband or the wife were the recipient. It is possible that FFW wages, if lower than the market wage for self-targeting purposes, may not necessarily improve women's outside options. However, opportunities for women to participate in the labor market are rare in rural Ethiopia. The earmarking of 80 percent of WFP's FFW operations to women, for example, would almost certainly improve their outside options.⁷

Time allocation to various activities, including farm production, home goods production, and FFW, could then be expressed as a function of the above right-hand-side variables. This paper investigates the impact of one form of unearned income, FD and FFW (which can be interpreted both as a change in the EEP as well as the wage vector) on child nutritional status, defined using the indicators weight-for-height and height-for-age.

⁶ See Haddad, Hoddinott, and Alderman (1997) for a review. For a more detailed exposition and derivation of the reduced form demand functions, see Thomas (1990).

⁷ In practice, where wages are determined by communities, they have not been set below the market wage. Instead, days are rationed to provide employment opportunities for more households (Sharp 1997).

3. Data

This paper uses all four rounds of the Ethiopian Rural Household Survey (ERHS). The 1997 round was undertaken by the Department of Economics of Addis Ababa University (AAU), in collaboration with the International Food Policy Research Institute (IFPRI) and the Center for the Study of African Economies (CSAE) of Oxford University. The first three rounds were conducted in 1994/95 by AAU and CSAE, building on an earlier IFPRI survey conducted in 1989. The ERHS covered approximately 1,500 households in 15 villages across Ethiopia. While sample households within villages were randomly selected, the villages themselves were chosen to ensure that the major farming systems are represented.⁸ Thus, although the 15 villages included in the sample are not statistically representative of rural Ethiopia as a whole, they are quite diverse and include all major agroecological, ethnic, and religious groups.⁹

The questionnaires for the first four rounds consist of a series of core modules on various issues such as consumption expenditures, wealth, income, and health, as well as a module on anthropometric measurements for all household members. The questionnaire used in the 1997 round includes the original core modules, supplemented with new modules specifically designed to address intrahousehold allocation issues. These modules were designed not only to be consistent with information gathered in the core modules, but also to complement individual-specific information.¹⁰ Because assets at marriage may determine spouses' bargaining power within marriage (Quisumbing and Maluccio 2000; Frankenberg and Thomas 2001), a variety of assets brought to the

⁸ About 400 households in six sites were initially surveyed by IFPRI in 1989; these were selected from drought-prone areas for the study by Webb, von Braun, and Yohannes (1992). Three more sites were added in 1994–1995 to include areas north of Debre Berhan, which could not be surveyed in 1989 due to military conflict. Six other sites were also added to cover the main agroclimatic zones and farming systems of the richer parts of the country. The selection of new sites is described in Bereket Kebede (1994).


⁹ See Fafchamps and Quisumbing (2002) for a discussion of the representativeness of the sample.

¹⁰ These are described in more detail in Fafchamps and Quisumbing (2002).

marriage were recorded, as were all transfers made at the time of marriage. Values of assets at marriage were converted to 1997 birr, using the consumer price index.¹¹

The location of the surveyed villages is depicted in Figure 1. Most surveyed villages are placed along a north-south axis. This ensures a good coverage of the various agroclimatic zones that characterize the Ethiopian highlands, where the bulk of the population lives. Arid lowlands and other regions that are particularly hard to reach, such as the western part of the country along the Sudanese border, were excluded from the sample for cost reasons. This may limit the policy conclusions on targeting that can be drawn.

Figure 1—Ethiopian Rural Household Survey (ERHS) sites



Source: UNDP-EUE 1998.

Note: All borders and survey site locations are approximate.

¹¹ See Fafchamps and Quisumbing (2002) for details.

Each survey round obtained information on income earned from various activities in the past four months, including FFW. For each activity, information was collected on the number of days worked, whether the payment was in cash or in kind, the value of cash payments, the quantity and unit of in-kind payments, and the identity of the income recipient. Respondents were also asked whether the household received food aid through free distribution, and which person in the household received it.¹² Most participants in both FD and FFW received their payments in kind, typically in wheat, maize, sorghum, and cooking oil; all in-kind receipts were converted to cash equivalents using the village-level price.

Table 1 presents descriptive statistics of the sample households, by survey round. About a quarter of the households participated in FFW over the four survey rounds. The proportion that benefited from FD was more variable, ranging from 11 percent in the 1995 round to 37 percent in the second 1994 round. There is also greater variation in FD compared to FFW receipts. FD payments were highest in the second round.¹³ FD and FFW contributed 2 to 7 percent of household monthly consumption across survey rounds.

Table 1 also presents information on individual rainfall and livestock disease shocks. All data on shocks are self-reported, based on recall of events in the last cropping season and the relevant harvest, and are used to construct indices of adverse occurrences affecting crop and livestock production.¹⁴ The broad categories of shocks are rainfall shocks, nonrain shocks (mostly common problems related to pests, flooding,

¹² Ideally we would have interviewed husbands and wives separately, but this was difficult in practice, since husbands did not want their wives to speak to male interviewers. Thus, with the exception of female heads of households, the respondent was the husband. If a woman wanted to conceal her food aid receipts from her husband, respondent reports would understate the true value of receipts. We did administer a module on indicators of bargaining power separately to husbands and wives, but only after the interviewers had resided in the village for a longer period.

¹³ The descriptive statistics pertain to the sample used in the estimation, and will be slightly different from those reported by Dercon and Krishnan (2000a). The estimation sample is slightly smaller than the full sample because it includes households present in all rounds and for which there is information on assets at marriage.

¹⁴ This description is taken mostly from Dercon and Krishnan (2000b); for comparability, this study used a very similar methodology for creating the shock index.

Table 1—Characteristics of sample households, by survey round, Ethiopia Rural Household Survey

	Survey round			
	1994a	1994b	1995	1997
Dummy for participant in food-for-work	0.27	0.26	0.26	0.24
Days worked in past four months (participants only)	36.40	40.90	35.82	36.55
Value of food-for-work payments received in past four months (participants only), in 1997 birr	113.66	121.73	125.82	131.66
Dummy for recipient of free distribution	0.12	0.37	0.11	0.18
Value of free distribution received in past four months (recipients only), in 1997 birr	115.45	237.14	65.76	58.97
Monthly consumption expenditure, net of free distribution and food-for-work, in 1997 birr	460.68	768.10	545.75	674.87
Monthly equivalent food-for-work receipts, whole sample	29.17	7.13	8.00	8.29
Monthly equivalent free distribution receipts, whole sample	3.60	19.03	1.38	2.00
Total monthly consumption, including free distribution and food-for-work, in 1997 birr	493.45	794.26	555.13	685.16
Contribution of food-for-work and free distribution to monthly consumption, percent	0.07	0.03	0.02	0.02
Rainfall index (1 is best)	0.51	0.48	0.62	0.52
Livestock disease index (1 is best)	0.74	0.89	0.89	0.98

insects, and animal trampling or weed damage), and livestock shocks. This paper focuses only on rainfall shocks and livestock disease shocks, since these tend to be common within villages and thus could be a proxy for aggregate shocks. The individual rainfall index was constructed to measure the farm-specific experience related to rainfall in the preceding season, based on such questions as whether plowing occurred too early or too late for the rain, whether it rained when harvesting, etc. Responses to each of the questions (either yes or no) were coded as favorable or unfavorable rainfall outcomes, and averaged over the number of questions asked so that the best outcome would be equal to 1 and the worst, zero. According to Dercon and Krishnan (2000b), the village-level variance accounted for 77 percent of total variance in the rainfall index. Similar questions were also asked regarding livestock; among the sub-indices referring to problems with livestock, this study focused on livestock disease, because contagion enables individual shocks to be easily shared within the community. Relatively speaking, livestock disease was quite important in the first round of data collection, particularly in the south.

Ethiopia's history of wars, droughts, and famines has taken its toll on the nutritional status of children (Table 2). Close to half of children between 0 and 9 years of age are stunted, an indicator of long-term nutritional deprivation.¹⁵ Wasting, an indicator of acute energy deficiency, ranges from 9 to 22 percent for children between 0 and 3 years of age. Boys' and girls' anthropometric indicators do not significantly differ between 0 and 3 years of age, but stunting becomes more prevalent for boys between ages 3 and 5 and remains so in the 5–9 age group; wasting is more prevalent among boys from ages 5 to 9 (Table 3).

Table 2—Trends in wasting and stunting, by survey round

	Survey round			
	1994a	1994b	1995	1997
Children 0 to 3 years				
Wasted	0.11	0.09	0.15	0.22
Stunted	0.51	0.5	0.52	0.66
Children 3 to 5 years				
Wasted	0.08	0.09	0.11	0.15
Stunted	0.53	0.53	0.52	0.57
Children 5 to 9 years				
Wasted	0.07	0.08	0.11	0.13
Stunted	0.46	0.48	0.43	0.52

Note: Wasting is defined as weight-for-height Z-score less than -2; stunting is defined as a height-for-age Z-score of less than -2.

Table 3—Weight-for-height and height-for-age Z-scores, by sex

	Weight-for-height Z-scores									
	Age 0–3			Age 3–5			Age 5–9			
	Number of observations	Mean	Standard Deviation	Number of observations	Mean	Standard Deviation	Number of observations	Mean	Standard Deviation	
Males	610	0.14	2.52	571	-0.33	1.56	1,050	-0.42	1.52	
Females	536	0.26	2.68	529	-0.29	1.62	1,172	-0.06	2.07	
t-test of difference		-0.76			-0.46			-4.59		
p-value		0.45			0.65			0.00		
	Height-for-age Z-scores									
Males	619	-2.61	2.22	573	-2.49	2.02	1,056	-2.22	1.82	
Females	543	-2.56	2.15	533	-2.27	2.06	1,177	-1.89	1.81	
t-test of difference		-0.38			-1.83			-4.35		
p-value		0.70			0.07			0.00		

¹⁵ Stunting is defined as having a height-for-age Z-score below -2 standard deviations from the NCHS standard; wasting is defined as a weight-for-height Z-score below -2.

4. Empirical Specification

The empirical portion of this paper consists of two parts. The first part examines the determinants of participation in FFW and FFW receipts, as well as the determinants of the probability of receiving FD and FD receipts.¹⁶ In addition to individual and family characteristics, the study includes household- and village-level rainfall and livestock disease shocks to investigate the extent to which households and individuals use food aid to mitigate the effects of these shocks. In the second part, the paper models current child nutritional status as a function of past nutritional status, receipts of FFW or FD, consumption net of food aid, and aggregate rainfall and livestock disease shocks.

Determinants of FFW and FD Receipts

Food aid is targeted using three methods: administrative targeting, using such indicators as asset or livestock ownership, age and gender, nutritional status, access to resources such as land and family labor; self-targeting, typically implemented using wages below the market wage rate and “inferior” goods; and community-based targeting, based on community decisions about the eligibility of households to participate in food aid programs (Clay, Molla, and Habtewold 1999). Thus, food aid receipts are not random and will depend on individual, household, and community characteristics. To take into account the endogeneity of participation in FFW and receipt of FD, this paper uses the Heckman procedure to correct for selectivity (Heckman 1979). The study assumes that the determinants of food aid receipts operate on two levels. First, the community decides which households are eligible for which type of program, based on program eligibility

¹⁶ Since the data are not nationally representative, this study does not examine the determinants of program placement, unlike Jayne et al. (2000), who examine *wereda*- (small regional unit) and household-level determinants of participation in food aid programs. This analysis is at a lower level of disaggregation—the household and the individual.

criteria; second, the individual within the eligible household decides to participate in the program.¹⁷ That is, the study attempts to estimate

$$F_j = X_j\beta + u_{1j}, \quad (10)$$

where F_j is the receipt of food aid, estimated separately for FFW and FD. F_j is observed only if

$$z_{j\gamma} + u_{2j} > 0, \quad (11)$$

where $u_1 \sim N(0, \sigma)$, $u_2 \sim N(0, 1)$, and $\text{corr}(u_1, u_2) = \rho$.

Equation (10) pertains to the determinants of individual receipts, while equation (11) is the (unobserved) selection process driven mostly by household characteristics. In the food aid receipts equation, the vector X_j contains individual characteristics such as the gender of the FFW participant or FD recipient, age, age squared, height, highest grade attained, household size and household composition variables, the value of assets at marriage (in 1997 birr) and the share of assets controlled by women, household rainfall and livestock disease indices, and village and round dummies. The household composition variables are the proportions in each age-sex demographic category, relative to males 15 to 65 years of age (the excluded category). In the selection equation, the vector z_j consists of a dummy for a female-headed household, household size and household composition variables, both asset-at-marriage variables, community-level rainfall and livestock disease indices, and round dummies. The community-level indices for each household were constructed by taking the average over all other households (i.e., excluding the particular household).¹⁸ The asset-at-marriage variables are used instead of current asset measures, since the latter are arguably endogenous to labor force and asset

¹⁷ Selection of households eligible for FD or FFW is done by local-level committee or by the community, although actual practice may differ across sites. Some individuals are predetermined to be eligible for FD—e.g., the old, sick, or disabled; lactating and pregnant women; persons who are required to care constantly for young children; or incapacitated adults. For details, see Sharp (1997, 22).

¹⁸ Although it would have been ideal to use actual rainfall data instead of self-reported rainfall data, data for all sites for the last survey round were not available.

accumulation decisions; using this set of variables also permits a specification consistent with a collective model of household decisionmaking.

Determinants of Child Nutritional Status

Child nutritional status is a cumulative measure that depends on inputs in past periods and possibly on past nutritional status as well (Strauss and Thomas 1995). A general child health and nutrition production function can be written as

$$H_t = f(H_{t-1}, X_i, X_h, X_c, u), \quad (12)$$

where subscript i denotes a child-level, h , a household-level, and c , a community-level covariate, and u represents unobserved heterogeneity. The input vector may include inputs of past periods as well as health, lagged several periods.

More specifically, child nutritional status can be written as a dynamic panel data model,

$$h_{it} = \sum h_{it-j} \alpha_j + \mathbf{x}_{it} \beta_1 + \mathbf{w}_{it} \beta_2 + v_i + \varepsilon_{it}, \quad (13)$$

where h_{it} is the nutritional status of child i in period t , h_{it-j} is nutritional status in the t - j th period, \mathbf{x}_{it} is a vector of exogenous covariates, \mathbf{w}_{it} is a vector of predetermined covariates, v_i are random effects that are independently and identically distributed over the individuals with variance σ_v^2 and ε_{it} is identically and independently distributed over the whole sample with variance σ_ε^2 . The dependent variables are weight-for-height and weight-for-age. The exogenous variables are household- and community-level rainfall and livestock disease shocks, while the predetermined variables, lagged one time period, are monthly consumption net of food aid, FA receipts (estimated separately for FFW and FD and also for the sum of both), the gender of the child interacted with the amount of

the receipt, and the gender of the child interacted with the gender of the aid recipient.¹⁹ The interaction terms indicate whether food aid has differential effects on children depending on their gender, and whether aid recipients have different preferences toward children based on gender. This model is estimated using the Arellano-Bond GMM estimator (Arellano and Bond 1991).

5. Results

Determinants of Participation in and Receipts from Food-for-Work and Food Aid Programs

Maximum likelihood estimates of the determinants of participation in FFW, days worked, and total FFW receipts are presented in Table 4. FFW participation appears to be self-targeted, with wealthier households less likely to participate. The share of assets held by women does not appear to affect the probability of participation, owing to the low share of women's assets for the majority of households (the median value of women's assets at marriage is zero). Larger households have a higher probability of participating in FFW. Households with a higher proportion of females between 15 and 65 years old are more likely to participate in FFW, but households with more females under 15 years of age are less likely to participate.²⁰ Participation in FFW responds as expected to

¹⁹ Although mother's height is an important determinant of child nutritional status, it is not an explanatory variable in the regressions. The Arellano and Bond (1991) dynamic panel data estimator addresses the problem of correlation of the lagged dependent variable with the error term by first differencing to remove the individual-specific random effects, and then using lagged levels of the dependent variable and predetermined variables and differences of the strictly exogenous variables as instruments. Individual-specific variables such as mothers' height that do not vary through time would drop out. However, if this study were to estimate this equation in levels, mother's height would be included. For example, Hoddinott and Kinsey (2002) include mother's height in least-squares regressions of growth in height of children, measured in centimeters per year, but mother's height drops out in the maternal fixed-effects estimates. While it is possible that the genetic potential for height can be fully expressed in the height-for-age Z-score of a newborn, it is more likely that the Z-score of the child of a tall mother will increase more in childhood relative to that of an average or short mother.

²⁰ This study disaggregated age groups further into children under 6 and children 6–15, but the results do not change. The aggregated results are presented here.

Table 4—Determinants of days worked and payments received, food-for-work program, Heckman maximum likelihood estimates**(Robust standard errors corrected for clustering on households.)**

	Days worked		Probability of participation		Payment received		Probability of participation	
	Coefficient	Z-score	Coefficient	Z-score	Coefficient	Z-score	Coefficient	Z-score
Female-headed household			-0.01	-0.03			0.01	0.03
Sex (1 = female)	0.60	0.20			-22.98	-1.19		
Age	-0.80	-1.75			3.78	1.02		
Age squared	0.01	1.82			-0.04	-0.88		
Height	0.15	1.11			-1.28	-1.66		
Highest grade	-0.68	-0.89			4.10	0.65		
Log household size	-0.40	-0.13	0.50	4.95	-21.29	-1.12	0.50	4.96
Males < 15	9.67	1.16	-0.23	-0.73	107.73	1.69	-0.23	-0.73
Females < 15	23.77	2.95	-0.80	-2.44	148.03	3.27	-0.80	-2.45
Females 15–65	18.18	2.24	0.89	2.48	9.18	0.19	0.89	2.48
Males 65+	136.11	3.65	-0.63	-0.94	876.48	2.24	-0.63	-0.94
Females 65+	-9.07	-0.26	-0.76	-0.92	103.04	0.71	-0.76	-0.92
Total assets at marriage	0.00	1.35	-0.00	-3.16	0.01	1.27	-0.00	-3.16
Share of women's assets	-1.32	-0.22	0.14	0.56	0.79	0.03	0.13	0.52
Rainfall index	-6.70	-2.47			-2.60	-0.15		
Livestock disease index	-0.38	-0.16			-5.47	-0.29		
Community rainfall index			-1.35	-8.00			-1.35	-7.99
Community livestock disease index			-1.29	-4.35			-1.30	-4.38
Geblen	6.65	1.47			-57.10	-1.28		
Dinki	-16.13	-3.85			-48.45	-1.17		
Shumshaha	36.53	1.28			284.62	1.13		
Adele Keke	4.39	0.64			-9.41	-0.16		
Trirufe Kechema	-13.44	-3.80			-65.25	-1.27		
Imdibir	-0.04	-0.01			-12.49	-0.32		
Gara Godo	27.04	6.57			43.10	0.96		
Doma	-15.12	-4.63			-43.37	-1.04		
Round 2 dummy	0.17	0.10	0.10	1.85	-6.34	-0.50	0.10	1.85
Round 3 dummy	-3.60	-2.06	-0.09	-1.52	-5.17	-0.49	-0.09	-1.51
Round 4 dummy	-4.57	-2.34	-0.11	-1.02	-11.81	-0.82	-0.10	-1.01
Constant	16.73	0.78	0.58	1.96	239.46	2.02	0.58	1.95
Log likelihood	-4,007.80		-5,231.75					
Test of independent equations:								
Chi-square (p-value)	1.24	(0.26)						
Number of observations	2,753							
Censored	2,139							
Uncensored	614							

Note: Z-statistics in bold are significant at 10 percent or better.

community rainfall and livestock disease shocks. Since the rainfall and disease indices are constructed so that more favorable outcomes are closer to unity, a higher value of the index is a positive shock, and thus the negative signs on the coefficients indicate that households are less likely to participate if they receive positive shocks. Contrary to the

findings of Clay, Molla, and Habtewold, this study does not find that female-headed households are more likely to participate in FFW (Clay, Molla, and Habtewold 1999). The test of independent equations (fourth line from bottom of Table 4) indicates that the receipts and days-worked equations can, in fact, be estimated independently of the selection equation.

Days worked in FFW are negatively related to schooling attainment of the FFW participant, but this coefficient is insignificant.²¹ Participants in households with a higher proportion of working-age females, as well as older males, tend to work more. The latter finding is consistent with that of Clay, Molla, and Habtewold (1999), who find that households with older male household heads tend to be disproportionately targeted in food aid interventions. Conditional on participation, household rainfall outcomes also affect days worked—individuals in households that experienced negative rainfall shocks worked more. FFW programs do not seem to discriminate against female participants, whose earnings are not significantly less than male FFW participants. Interestingly, FFW payments appear to be weakly negatively correlated with height. This may be due to an institutional feature of FFW in Ethiopia. In many cases, the desire to spread the benefits of FFW thinly has led communities to share individual rations among a large number of households (Sharp 1997). If quotas are small, for example, the local committee may cut the number of workplaces or rations given to each household rather than reduce the number of families assisted, so payments would no longer be directly linked to work effort. In some areas, FFW is also organized on a part-time basis so that participants can continue with farming or other work. Able-bodied participants who are still farming could therefore devote less time to FFW and thus would earn less than those without outside activities.

Payments are also higher if the participant belongs to a household with a higher proportion of males and females under 15, and with a larger ratio of males over 65 years

²¹ The coefficient on schooling was negative and significant in the specification that did not include height. Schooling and height may thus represent alternative forms of human capital stocks.

of age, conditional on participation. If these demographic groups are more vulnerable to shocks, then payments do seem to provide some protection to them. While larger households have a higher probability of participating in FFW, household size does not significantly affect actual receipts, probably due to de jure rules whereby only one member of the household is allowed to work (Jayne et al. 2002).

In contrast to FFW, FD participation, which is determined by the community, does not appear to be targeted on the basis of household wealth (Table 5). Larger households surprisingly have a lower probability of receiving FD.²² However, households with a larger proportion of young members, both male and female, also have a higher probability of receiving FD. Lastly, the probability of receiving FD responds to aggregate community rainfall and livestock disease shocks: better rainfall and livestock health outcomes reduce the probability of participation. Turning to FD receipts, the only significant determinant of receipts is household assets: individuals from wealthier households receive less FD. Individual FD receipts do not appear to be affected by individual shocks, suggesting that FD is probably targeted at the community level. Unlike the results shown in Table 4, the test of independent equations confirms that the FD receipt equation (fourth line from bottom of Table 5) cannot be estimated independently of the selection equation.

Impact of Food-for-Work and Food Aid on Child Nutritional Status

To assess whether food aid has an impact on child nutritional status, this study runs regressions on weight-for-age Z-scores and height-for-age Z-scores separately on children from 0 to 5 years old and from 5 to 9 years old, for low-asset and high-asset households. Results for low-asset households are presented in Table 6, and for high-asset households in Table 7. Regressors include the lagged change in the anthropometric

²² Jayne et al. (2002) also find a negative relationship between per capita food aid receipts and household size. The negative relationship turns positive when household FFW receipts rather than per capita receipts are used as the dependent variable.

Table 5—Determinants of food distribution receipts, Heckman maximum likelihood estimates

(Robust standard errors corrected for clustering on households.)

	FD receipts		Probability of receiving FD	
	Coefficient	Z-score	Coefficient	Z-score
Female-headed household			-0.17	-1.21
Sex (1=female)	-24.73	-0.43		
Age	4.30	0.41		
Age squared	-0.01	-0.07		
Height	-2.73	-0.94		
Highest grade	8.42	1.27		
Log household size	1.56	0.02	-0.27	-3.32
Males < 15	225.18	0.86	0.61	2.52
Females < 15	-274.98	-1.05	0.55	2.08
Females 15–65	48.52	0.19	-0.10	-0.38
Males 65+	78.61	0.14	0.33	0.65
Females 65+	-215.31	-0.66	-0.16	-0.22
Total assets at marriage	-0.01	-2.10	0.00	1.31
Share of women's assets	-11.36	-0.15	0.20	1.17
Rainfall index	35.85	0.73		
Livestock disease index	69.31	1.36		
Community rainfall index			-2.48	-14.57
Community livestock disease index			-1.45	-9.54
Geblen	-38.61	-0.14		
Dinki	15.76	0.06		
Shumshaha	298.46	1.04		
Sirbana Godeti	139.00	0.46		
Adele Keke	285.00	1.00		
Korodegaga	190.67	0.68		
Trirufe Kechemma	8.49	0.03		
Imdibir	170.76	0.62		
Aze Deboa	431.58	1.45		
Gara Godo	240.03	0.85		
Doma	-94.02	-0.34		
Debre Berhan	137.97	0.44		
Round 2 dummy	324.85	2.33	1.10	11.49
Round 3 dummy	27.16	0.41	-0.17	-1.97
Round 4 dummy	-75.16	-1.98	-0.00	-0.07
Constant	181.87	0.49	1.66	9.23
Log likelihood	-4,523.48			
Test of independent equations:				
Chi-square (p-value)	10.46	(0.00)		
Number of observations	2,818			
Censored	2,360			
Uncensored	458			

Note: Z-statistics in bold are significant at 10 percent or better.

measure, first differences in the following variables: the child's age and age squared, household consumption expenditure net of food aid and food for work, community livestock and rainfall shocks, and the interactions of the shock variables with child sex,

round dummies, and first differences and lagged differences in food for work, free distribution, the value of the aid receipt times a dummy for a female child, and the interaction of a dummy variable for a female aid recipient with a dummy variable for a female child. Only the coefficients of the aid variables are presented here. The explanatory variables are expressed either in lags or in first differences, eliminating variables that do not vary across time. Since the sample consists of children for whom

Table 6—Effects of FD and FFW on child weight-for-height and height-for-age, low-asset households

	Weight-for-height				Height-for-age			
	Children 0–4.9		Children 5–8.9		Children 0–4.9		Children 5–8.9	
	Coefficient	Z-score	Coefficient	Z-score	Coefficient	Z-score	Coefficient	Z-score
Number of observations	306		415		311		420	
Low-asset households (assets less than or equal to median assets)								
Value of FFW								
First difference	0.05	1.93	0.01	1.30	–0.04	–1.73	0.00	0.85
Lagged difference	–0.02	–0.47	0.01	1.04	0.02	0.60	0.00	0.37
Girl x FFW receipt								
First difference	–0.09	–1.78	–0.01	–0.44	0.02	0.38	–0.00	–0.05
Lagged difference	–0.02	–0.29	0.00	0.03	–0.05	–0.64	–0.08	–1.99
Girl x female participant								
First difference	–3.81	–0.29	0.05	0.02	–4.51	–0.33	0.23	0.07
Lagged difference	–3.13	–0.25	0.02	0.03	–5.85	–0.44	–0.58	–0.47
Value of FD								
First difference	–0.00	–0.65	0.00	0.10	–0.00	–0.58	0.00	0.18
Lagged difference	0.00	0.30	0.00	1.42	–0.00	–0.86	0.00	0.09
Girl x FD receipt								
First difference	0.00	0.56	0.00	0.29	–0.01	–1.19	–0.00	–0.39
Lagged difference	0.01	1.19	–0.00	–0.71	–0.01	–1.34	–0.00	–0.00
Girl x female recipient								
First difference	1.58	0.43	4.26	1.22	–3.58	–0.92	–0.11	–0.04
Lagged difference	–1.62	–0.87	–3.98	–2.93	1.45	0.80	–0.06	–0.05
Value of FFW and FD								
First difference	0.01	1.35	0.00	0.52	–0.01	–1.38	–0.00	–0.38
Lagged difference	0.00	0.63	0.00	2.61	–0.00	–1.00	–0.00	–0.15
Girl x total value of receipts								
First difference	–0.06	–0.66	–0.00	–0.31	–0.01	–1.31	0.00	0.50
Lagged difference	0.01	1.02	–0.00	–0.88	–0.02	–2.94	0.00	0.17
Girl x female FFW participant								
First difference	2.92	0.37	–9.08	–1.21	–0.73	–0.11	6.91	1.07
Lagged difference	2.28	0.29	1.37	0.56	–2.52	–0.40	0.05	0.04
Girl x female FD recipient								
First difference	1.16	0.30	4.54	1.65	0.84	0.31	–3.72	–1.41
Lagged difference	–0.64	–0.32	–3.68	–2.47	2.62	1.87	–0.09	–0.09

Notes: Regressors include lagged change in weight-for-height Z-scores, and first differences in net expenditure, age, age squared, community livestock and rainfall shocks, and interactions of the shock variables with child sex, and round dummies. Z-values in bold are significant at 10 percent or better.

Table 7—Effects of free distribution (FD) and food-for-work (FFW) on child weight-for-height and height-for-age, high-asset households

	Weight-for-height				Height-for-age			
	Children 0–4.9		Children 5–8.9		Children 0–4.9		Children 5–8.9	
	Coefficient	Z-score	Coefficient	Z-score	Coefficient	Z-score	Coefficient	Z-score
High-asset households (assets greater than median assets)								
Number of observations	319		431		328		438	
Value of FFW								
First difference	-0.01	-0.93	-0.01	-0.46	0.00	0.10	-0.01	-0.54
Lagged difference	-0.02	-0.76	-0.06	-0.76	0.01	0.29	-0.01	-0.19
Girl x FFW receipt								
First difference	-0.01	-0.32	0.01	0.31	0.12	0.95	0.00	0.17
Lagged difference	-0.31	-2.25	0.07	0.97	0.19	0.95	0.00	0.11
Girl x female participant								
First difference	4.43	0.75	-1.58	-0.47	-6.87	-0.86	-2.46	-1.27
Lagged difference	-1.00	-0.43	0.51	0.16	0.58	0.20	-2.02	-0.81
Value of FD								
First difference	-0.01	-0.91	-0.00	-0.04	0.00	0.78	0.00	0.06
Lagged difference	0.00	2.25	0.00	1.93	0.00	0.82	-0.00	-3.86
Girl x FD receipt								
First difference	-0.00	-0.25	-0.00	-0.16	0.01	1.26	0.00	0.15
Lagged difference	0.01	2.06	0.00	1.86	0.00	0.79	0.00	0.12
Girl x female recipient								
First difference	3.01	1.53	3.63	2.24	0.01	0.00	-1.11	-0.68
Lagged difference	-2.16	-1.53	-2.65	-2.17	-0.67	-0.62	0.81	1.26
Value of FFW and FD								
First difference	-0.00	-0.47	-0.00	-0.03	-0.00	-0.34	-0.00	-0.44
Lagged difference	0.00	2.45	0.00	1.84	0.00	1.04	-0.00	-4.01
Girl x total value of receipts								
First difference	-0.00	-0.35	0.00	0.12	0.00	1.36	-0.00	-0.02
Lagged difference	0.00	0.65	0.00	1.83	0.00	0.39	-0.00	-0.37
Girl x female FFW participant								
First difference	15.34	1.23	-3.57	-1.42	-10.25	-0.83	-1.81	-0.95
Lagged difference	3.45	0.99	-0.93	-0.67	-1.56	-0.60	-1.55	-1.24
Girl x female FD recipient								
First difference	4.51	1.59	2.77	1.73	-0.07	-0.04	-0.01	-0.01
Lagged difference	-1.40	-0.50	-2.60	-2.16	0.26	0.26	1.43	1.60

Notes: Regressors include lagged change in weight-for-height Z-scores, and first differences in net expenditure, age, age squared, community livestock and rainfall shocks, and interactions of the shock variables with child sex, and round dummies. Z-values in bold are significant at 10 percent or better.

we have observations on all four rounds within each age group, and because the differencing procedure reduces the number of observations used in estimation, the sample size used for estimation is much smaller than the original sample size of children.²³

Regression results for low-asset households (Table 6) show that both FFW and FD have gender-differentiated impacts. FFW has a positive direct impact on weight-for-height for children ages 0 to 5 in low-asset households, although there is weak evidence that FFW has improves boys' weight-for-height more than it does girls'. This effect does not depend on the gender of the aid recipient. In contrast, among older children, if FD is received by a woman, it results in an improvement of boys' weight-for-height relative to that of girls. The lagged difference of total aid receipts has a positive impact on weight-for-height of older children. The effects of the interaction of child sex and a female recipient in the combined aid regression do not show a consistent pattern of gender preference.

Since height-for-age is a measure of long-term nutritional status, it is not as responsive to food aid interventions in the short run as is weight-for-height. This study finds that FFW has a weak negative impact on height-for-age of younger children. Similar to the effects on weight-for-height, total food aid receipts seem to improve boys' height-for-age more it does girls'. If a woman is the FD recipient, however, this weakly favors younger girls. Height-for-age of older children is less responsive to food aid partly because height growth slows down for older children. The only significant food aid variable (the lagged difference in FFW receipts interacted with the female child dummy) suggests that FFW receipts tend to improve boys' long-run nutritional status relative to girls.

Do these effects differ for high-asset households? Among younger children, FFW receipts improve boys' weight-for-height relative to girls. In contrast, FD has both a

²³ Attrition bias may arise because children who remain in the sample for all four rounds may be better nourished than those who leave the sample (as in child death due to undernutrition). However, in this analysis, the reduction in sample size arose mainly because of the differencing procedure and the age criterion used to define the sample for estimation.

positive direct effect on weight-for-height for both older and younger children, and tends to benefit girls. Total food aid receipts, regardless of modality, improve weight-for-height, and weakly favor girls. The effects of the gender of the FD recipient on girls are not consistent, with the first difference showing a positive effect, and the lagged difference a negative one. Consistent with the relative insensitivity of height-for-age to short-run interventions, the aid variables have a negligible impact on height-for-age. Although not reported in the tables, the strongest determinant of height-for-age is the lagged change in height-for-age. There is an indication, however, that FD receipts have a lagged negative effect on height-for-age of older children, although the coefficients are very small in magnitude.

To summarize, FFW has a positive direct impact on the weight-for-height of younger children in low asset households, while FD has a similar positive impact on children of both age groups in high-asset households. The effect of FFW on low-asset households probably reflects its self-targeting features. Does food aid have a differential effect on child gender, depending on its modality? In both low- and high-asset households, FFW receipts appear to be invested in improving boys' nutritional status relative to girls, while in high-asset households, girls' nutritional status improves with FD. The effects of a female recipient of food aid are inconsistent. To interpret these results, we return to the collective model of the household. FD receipts, which are not conditional on work effort, can be considered a form of unearned income. FFW opportunities, on the other hand, reflect a change in the wage rate as well as improvements in women's outside options. Increases in the households' unearned income from FD are invested in girls, but changes in the wage rate and in women's outside options from FFW translate into better outcomes for boys.

6. Conclusions and Policy Implications

This paper has examined the effects of food aid on child nutritional status through two complementary analyses: one of the determinants of participation in, and receipts

from, two types of food aid programs, and investigation of the effects of food aid on child nutritional status. The analysis of both FD and FFW receipts shows that these increase with negative rainfall and livestock shocks, thus performing an important consumption-smoothing function. Participation in FFW also seems to be well-targeted to poorer households. While participation in FD seems to be motivated more by household characteristics such as the presence of young children rather than household wealth, FD receipts do decline with wealth. Thus, both programs are also reaching poorer and more vulnerable households in their communities. The analysis at the first level, however, does not reveal who in the household benefits from aid received. The analysis of child nutritional status shows that the effects of food aid on individuals within the household differ, depending on the modality of food aid and the gender of the child. Both FFW and FD have a positive direct impact on weight-for-height, which is expected to respond more to these interventions in the short run. Households seem to invest proceeds from FD, which can be interpreted as an increase in unearned income, in girls' nutrition, while earnings from FFW are manifested in better nutrition in boys. The effects of the gender of the aid recipient are not conclusive.

Why would different forms of transfer income be invested differentially depending on the gender of the child? First, parents may want to use some forms of aid to redress imbalances among children. Nutritional status indicators, while poor for both boys and girls, become progressively worse for boys (see Table 3). Second, it may be due to returns that parents expect to reap from children in their old age. In related work using the same data set, Quisumbing and Maluccio (2000) find that daughters of mothers who bring more resources to the union have inferior educational outcomes than do their brothers. If boys are important sources of old-age security, mothers may choose to invest preferentially in boys. If FFW is increasingly targeted to women, mothers may use their increased bargaining power to preferentially invest in boys. A general increase in household wealth, however, operating through FD receipts, may result in better outcomes for girls.

These findings suggest that stopping at the household level to assess the impact of food aid may not reveal how the modality of food aid affects investments in the next generation. The effects of food aid are not limited to its effects on unearned income and women's outside options. Children's time allocation may also change, depending on the modality of food aid (Yamano 2000). Participation in FFW may also affect time allocation and nutritional status of participants. While participation in demanding physical labor such as FFW may improve children's nutritional outcomes, it may lead to a deterioration in the participants' own nutritional status as well as a reallocation of time away from the production of home goods, again with implications for child health and nutrition.²⁴

Program designers need to examine the impact of food aid on individual outcomes, both for adults and for the next generation, to better assess food aid's long-term impact.

²⁴ Evidence that increased physical labor is detrimental to nutritional status can be found in Higgins and Alderman (1997).

References

- Arellano, M., and S. Bond. 1991. Some tests of specification for panel data: Monte Carlo evidence and an application to employment equations. *Review of Economic Studies* 58 (2): 277–297.
- Barrett, C. B. 2002. Food security and food assistance programs. In *Handbook of agricultural economics*, ed. B. C. Gardner and G. C. Rausser. Amsterdam: Elsevier Science.
- Barrett, C. B., and D. C. Clay. 2001. How accurate is food-for-work self-targeting in the presence of imperfect factor markets? Evidence from Ethiopia. Manuscript. Cornell University, Ithaca, N.Y., U.S.A.
- Behrman, J. R. 1997. Intrahousehold distribution and the family. In *Handbook of population and family economics*, ed. M. R. Rosenzweig and O. Stark. Amsterdam: North-Holland Publishing Company.
- Brown, L. R., Y. Yohannes, and P. Webb. 1994. Rural labor-intensive public works: Impacts of participation on preschooler nutrition: Evidence from Niger. *American Journal of Agricultural Economics* 76 (5): 1213–1218.
- Clay, D. C., D. Molla, and D. Habtewold. 1999. Food aid targeting in Ethiopia: A study of who needs it and who gets it. *Food Policy* 24 (4): 391–409.
- Dercon, S., and P. Krishnan. 2000a. Risk-sharing within households in rural Ethiopia. *Journal of Political Economy* 108 (4): 688–727.
- _____. 2000b. Vulnerability, seasonality, and poverty in Ethiopia. *Journal of Development Studies* 36 (6): 25–53.
- Fafchamps, M., and A. R. Quisumbing. 2002. Control and ownership of assets within rural Ethiopian households. *Journal of Development Studies* 38 (6): 47–82.
- Ethiopia (Federal Democratic Republic of). 1996. *Food security strategy 1996*. Addis Ababa.

- Frankenberg, E., and D. Thomas. 2001. *Measuring power*. Food Consumption and Nutrition Division Discussion Paper 113. Washington, D.C.: International Food Policy Research Institute.
- Haddad, L., J. Hoddinott, and H. Alderman, eds. 1997. *Intrahousehold resource allocation in developing countries: Methods, models, and policy*. Baltimore, Md., U.S.A.: Johns Hopkins University Press for the International Food Policy Research Institute.
- Heckman, J. J. 1979. Sample selection bias as a specification error. *Econometrica* 47 (1): 153–161.
- Higgins, P., and H. Alderman. 1997. Labor and women's nutrition: The impact of work effort and fertility on nutritional status in Ghana. *Journal of Human Resources* 32 (3): 577–595.
- Hoddinott, J., and B. Kinsey. 2002. Child growth in the time of drought. *Oxford Bulletin of Economics and Statistics* 63 (4): 409–436.
- Kebede, B. 1994. Report on site selection, Ethiopia Rural Household Survey 1994. Centre for the Study of African Economics, Oxford University, and Department of Economics, Addis Ababa University. Photocopy.
- Jayne, T., J. Strauss, T. Yamano, and J. Molla. 2002. Targeting of food aid in rural Ethiopia: Chronic need or inertia? *Journal of Development Economics* 68 (2): 247–288.
- Quisumbing, A. R., and J. A. Maluccio. 2000. *Intrahousehold allocation and gender relations: New empirical evidence from four developing countries*. Food Consumption and Nutrition Division Discussion Paper 84. Washington, D.C.: International Food Policy Research Institute.
- Rogers, B. L. 1988. Design and implementation considerations for consumer food price subsidies. In *Food subsidies in developing countries: Costs, benefits and policy options*, ed. P. Pinstrup-Andersen. Baltimore, Md., U.S.A.: Johns Hopkins University Press for the International Food Policy Research Institute.

- Sharp, K. 1997. Targeting food aid in Ethiopia. Save the Children Fund (UK), Addis Ababa.
- Skoufias, E. 2003. *PROGRESA and its impacts on the human capital and welfare of households in rural Mexico: A synthesis of the results of an evaluation by IFPRI*. Research Report. Washington, D.C.: International Food Policy Research Institute. Forthcoming.
- Strauss, J. A., and D. Thomas. 1995. Human resources: Empirical modeling of household and family decisions. In *Handbook of development economics*, ed. T. N. Srinivasan and J. Behrman. Amsterdam: North Holland.
- Thomas, D. 1990. Intrahousehold resource allocation: An inferential approach. *Journal of Human Resources* 25 (3): 635–664.
- UNDP/EUE (United Nations Development Programme/Emergencies Unit in Ethiopia). 1999. Map of Ethiopia with regional borders. <http://www.sas.upenn.edu/African_Studies/eue_web/graphics/newzones.gif>. Updated February 15, 1999; accessed May 16, 1999.
- Webb, P., and S. Kumar. 1995. Food and cash for work in Ethiopia: Experiences during famine and macroeconomic reform. In *Employment for poverty reduction and food security*, ed. J. Von Braun. Washington, D.C.: International Food Policy Research Institute.
- Webb, P., J. von Braun, and Y. Yohannes. 1992. *Famine in Ethiopia: Policy implications of coping failure at national and household levels*. Research Report 92. Washington, D.C.: International Food Policy Research Institute.
- WFP (World Food Programme). 1996. *WFP's commitments to women*. Rome.
- Yamano, T. 2000. The effects of food aid and household composition on child farm labor supply in rural Ethiopia. Manuscript. Department of Agricultural Economics, Michigan State University, East Lansing, Mich., U.S.A.

FCND DISCUSSION PAPERS

- 157 *HIV/AIDS, Food Security, and Rural Livelihoods: Understanding and Responding*, Michael Loevinsohn and Stuart Gillespie, September 2003
- 156 *Public Policy, Food Markets, and Household Coping Strategies in Bangladesh: Lessons from the 1998 Floods*, Carlo del Ninno, Paul A. Dorosh, and Lisa C. Smith, September 2003
- 155 *Consumption Insurance and Vulnerability to Poverty: A Synthesis of the Evidence from Bangladesh, Ethiopia, Mali, Mexico, and Russia*, Emmanuel Skoufias and Agnes R. Quisumbing, August 2003
- 154 *Cultivating Nutrition: A Survey of Viewpoints on Integrating Agriculture and Nutrition*, Carol E. Levin, Jennifer Long, Kenneth R. Simler, and Charlotte Johnson-Welch, July 2003
- 153 *Maquiladoras and Market Mamas: Women's Work and Childcare in Guatemala City and Accra*, Agnes R. Quisumbing, Kelly Hallman, and Marie T. Ruel, June 2003
- 152 *Income Diversification in Zimbabwe: Welfare Implications From Urban and Rural Areas*, Lire Ersado, June 2003
- 151 *Childcare and Work: Joint Decisions Among Women in Poor Neighborhoods of Guatemala City*, Kelly Hallman, Agnes R. Quisumbing, Marie T. Ruel, and Bénédicte de la Brière, June 2003
- 150 *The Impact of PROGRESA on Food Consumption*, John Hoddinott and Emmanuel Skoufias, May 2003
- 149 *Do Crowded Classrooms Crowd Out Learning? Evidence From the Food for Education Program in Bangladesh*, Akhter U. Ahmed and Mary Arends-Kuenning, May 2003
- 148 *Stunted Child-Overweight Mother Pairs: An Emerging Policy Concern?* James L. Garrett and Marie T. Ruel, April 2003
- 147 *Are Neighbors Equal? Estimating Local Inequality in Three Developing Countries*, Chris Elbers, Peter Lanjouw, Johan Mistiaen, Berk Özler, and Kenneth Simler, April 2003
- 146 *Moving Forward with Complementary Feeding: Indicators and Research Priorities*, Marie T. Ruel, Kenneth H. Brown, and Laura E. Caulfield, April 2003
- 145 *Child Labor and School Decisions in Urban and Rural Areas: Cross Country Evidence*, Lire Ersado, December 2002
- 144 *Targeting Outcomes Redux*, David Coady, Margaret Grosh, and John Hoddinott, December 2002
- 143 *Progress in Developing an Infant and Child Feeding Index: An Example Using the Ethiopia Demographic and Health Survey 2000*, Mary Arimond and Marie T. Ruel, December 2002
- 142 *Social Capital and Coping With Economic Shocks: An Analysis of Stunting of South African Children*, Michael R. Carter and John A. Maluccio, December 2002
- 141 *The Sensitivity of Calorie-Income Demand Elasticity to Price Changes: Evidence from Indonesia*, Emmanuel Skoufias, November 2002
- 140 *Is Dietary Diversity an Indicator of Food Security or Dietary Quality? A Review of Measurement Issues and Research Needs*, Marie T. Ruel, November 2002
- 139 *Can South Africa Afford to Become Africa's First Welfare State?* James Thurlow, October 2002
- 138 *The Food for Education Program in Bangladesh: An Evaluation of its Impact on Educational Attainment and Food Security*, Akhter U. Ahmed and Carlo del Ninno, September 2002
- 137 *Reducing Child Undernutrition: How Far Does Income Growth Take Us?* Lawrence Haddad, Harold Alderman, Simon Appleton, Lina Song, and Yisehac Yohannes, August 2002
- 136 *Dietary Diversity as a Food Security Indicator*, John Hoddinott and Yisehac Yohannes, June 2002
- 135 *Trust, Membership in Groups, and Household Welfare: Evidence from KwaZulu-Natal, South Africa*, Lawrence Haddad and John A. Maluccio, May 2002
- 134 *In-Kind Transfers and Household Food Consumption: Implications for Targeted Food Programs in Bangladesh*, Carlo del Ninno and Paul A. Dorosh, May 2002
- 133 *Avoiding Chronic and Transitory Poverty: Evidence From Egypt, 1997-99*, Lawrence Haddad and Akhter U. Ahmed, May 2002
-

FCND DISCUSSION PAPERS

- 132 *Weighing What's Practical: Proxy Means Tests for Targeting Food Subsidies in Egypt*, Akhter U. Ahmed and Howarth E. Bouis, May 2002
- 131 *Does Subsidized Childcare Help Poor Working Women in Urban Areas? Evaluation of a Government-Sponsored Program in Guatemala City*, Marie T. Ruel, Bénédicte de la Brière, Kelly Hallman, Agnes Quisumbing, and Nora Coj, April 2002
- 130 *Creating a Child Feeding Index Using the Demographic and Health Surveys: An Example from Latin America*, Marie T. Ruel and Purnima Menon, April 2002
- 129 *Labor Market Shocks and Their Impacts on Work and Schooling: Evidence from Urban Mexico*, Emmanuel Skoufias and Susan W. Parker, March 2002
- 128 *Assessing the Impact of Agricultural Research on Poverty Using the Sustainable Livelihoods Framework*, Michelle Adato and Ruth Meinzen-Dick, March 2002
- 127 *A Cost-Effectiveness Analysis of Demand- and Supply-Side Education Interventions: The Case of PROGRESA in Mexico*, David P. Coady and Susan W. Parker, March 2002
- 126 *Health Care Demand in Rural Mozambique: Evidence from the 1996/97 Household Survey*, Magnus Lindelow, February 2002
- 125 *Are the Welfare Losses from Imperfect Targeting Important?*, Emmanuel Skoufias and David Coady, January 2002
- 124 *The Robustness of Poverty Profiles Reconsidered*, Finn Tarp, Kenneth Simler, Cristina Matusse, Rasmus Heltberg, and Gabriel Dava, January 2002
- 123 *Conditional Cash Transfers and Their Impact on Child Work and Schooling: Evidence from the PROGRESA Program in Mexico*, Emmanuel Skoufias and Susan W. Parker, October 2001
- 122 *Strengthening Public Safety Nets: Can the Informal Sector Show the Way?*, Jonathan Morduch and Manohar Sharma, September 2001
- 121 *Targeting Poverty Through Community-Based Public Works Programs: A Cross-Disciplinary Assessment of Recent Experience in South Africa*, Michelle Adato and Lawrence Haddad, August 2001
- 120 *Control and Ownership of Assets Within Rural Ethiopian Households*, Marcel Fafchamps and Agnes R. Quisumbing, August 2001
- 119 *Assessing Care: Progress Towards the Measurement of Selected Childcare and Feeding Practices, and Implications for Programs*, Mary Arimond and Marie T. Ruel, August 2001
- 118 *Is PROGRESA Working? Summary of the Results of an Evaluation by IFPRI*, Emmanuel Skoufias and Bonnie McClafferty, July 2001
- 117 *Evaluation of the Distributional Power of PROGRESA's Cash Transfers in Mexico*, David P. Coady, July 2001
- 116 *A Multiple-Method Approach to Studying Childcare in an Urban Environment: The Case of Accra, Ghana*, Marie T. Ruel, Margaret Armar-Klemesu, and Mary Arimond, June 2001
- 115 *Are Women Overrepresented Among the Poor? An Analysis of Poverty in Ten Developing Countries*, Agnes R. Quisumbing, Lawrence Haddad, and Christina Peña, June 2001
- 114 *Distribution, Growth, and Performance of Microfinance Institutions in Africa, Asia, and Latin America*, Cécile Lapenu and Manfred Zeller, June 2001
- 113 *Measuring Power*, Elizabeth Frankenberg and Duncan Thomas, June 2001
- 112 *Effective Food and Nutrition Policy Responses to HIV/AIDS: What We Know and What We Need to Know*, Lawrence Haddad and Stuart Gillespie, June 2001
- 111 *An Operational Tool for Evaluating Poverty Outreach of Development Policies and Projects*, Manfred Zeller, Manohar Sharma, Carla Henry, and Cécile Lapenu, June 2001
- 110 *Evaluating Transfer Programs Within a General Equilibrium Framework*, Dave Coady and Rebecca Lee Harris, June 2001
-

FCND DISCUSSION PAPERS

- 109 *Does Cash Crop Adoption Detract From Childcare Provision? Evidence From Rural Nepal*, Michael J. Paolisso, Kelly Hallman, Lawrence Haddad, and Shibesh Regmi, April 2001
- 108 *How Efficiently Do Employment Programs Transfer Benefits to the Poor? Evidence from South Africa*, Lawrence Haddad and Michelle Adato, April 2001
- 107 *Rapid Assessments in Urban Areas: Lessons from Bangladesh and Tanzania*, James L. Garrett and Jeanne Downen, April 2001
- 106 *Strengthening Capacity to Improve Nutrition*, Stuart Gillespie, March 2001
- 105 *The Nutritional Transition and Diet-Related Chronic Diseases in Asia: Implications for Prevention*, Barry M. Popkin, Sue Horton, and Soowon Kim, March 2001
- 104 *An Evaluation of the Impact of PROGRESA on Preschool Child Height*, Jere R. Behrman and John Hoddinott, March 2001
- 103 *Targeting the Poor in Mexico: An Evaluation of the Selection of Households for PROGRESA*, Emmanuel Skoufias, Benjamin Davis, and Sergio de la Vega, March 2001
- 102 *School Subsidies for the Poor: Evaluating a Mexican Strategy for Reducing Poverty*, T. Paul Schultz, March 2001
- 101 *Poverty, Inequality, and Spillover in Mexico's Education, Health, and Nutrition Program*, Sudhanshu Handa, Mari-Carmen Huerta, Raul Perez, and Beatriz Traffon, March 2001
- 100 *On the Targeting and Redistributive Efficiencies of Alternative Transfer Instruments*, David Coady and Emmanuel Skoufias, March 2001
- 99 *Cash Transfer Programs with Income Multipliers: PROCAMPO in Mexico*, Elisabeth Sadoulet, Alain de Janvry, and Benjamin Davis, January 2001
- 98 *Participation and Poverty Reduction: Issues, Theory, and New Evidence from South Africa*, John Hoddinott, Michelle Adato, Tim Besley, and Lawrence Haddad, January 2001
- 97 *Socioeconomic Differentials in Child Stunting Are Consistently Larger in Urban Than in Rural Areas*, Purnima Menon, Marie T. Ruel, and Saul S. Morris, December 2000
- 96 *Attrition in Longitudinal Household Survey Data: Some Tests for Three Developing-Country Samples*, Harold Alderman, Jere R. Behrman, Hans-Peter Kohler, John A. Maluccio, Susan Cotts Watkins, October 2000
- 95 *Attrition in the Kwazulu Natal Income Dynamics Study 1993-1998*, John Maluccio, October 2000
- 94 *Targeting Urban Malnutrition: A Multicity Analysis of the Spatial Distribution of Childhood Nutritional Status*, Saul Sutkover Morris, September 2000
- 93 *Mother-Father Resource Control, Marriage Payments, and Girl-Boy Health in Rural Bangladesh*, Kelly K. Hallman, September 2000
- 92 *Assessing the Potential for Food-Based Strategies to Reduce Vitamin A and Iron Deficiencies: A Review of Recent Evidence*, Marie T. Ruel and Carol E. Levin, July 2000
- 91 *Comparing Village Characteristics Derived From Rapid Appraisals and Household Surveys: A Tale From Northern Mali*, Luc Christiaensen, John Hoddinott, and Gilles Bergeron, July 2000
- 90 *Empirical Measurements of Households' Access to Credit and Credit Constraints in Developing Countries: Methodological Issues and Evidence*, Aliou Diagne, Manfred Zeller, and Manohar Sharma, July 2000
- 89 *The Role of the State in Promoting Microfinance Institutions*, Cécile Lapenu, June 2000
- 88 *The Determinants of Employment Status in Egypt*, Ragui Assaad, Fatma El-Hamidi, and Akhter U. Ahmed, June 2000
- 87 *Changes in Intra-household Labor Allocation to Environmental Goods Collection: A Case Study from Rural Nepal*, Priscilla A. Cooke, May 2000
- 86 *Women's Assets and Intra-household Allocation in Rural Bangladesh: Testing Measures of Bargaining Power*, Agnes R. Quisumbing and Bénédicte de la Brière, April 2000
-

FCND DISCUSSION PAPERS

- 85 *Intrahousehold Impact of Transfer of Modern Agricultural Technology: A Gender Perspective*, Ruchira Tabassum Naved, April 2000
- 84 *Intrahousehold Allocation and Gender Relations: New Empirical Evidence from Four Developing Countries*, Agnes R. Quisumbing and John A. Maluccio, April 2000
- 83 *Quality or Quantity? The Supply-Side Determinants of Primary Schooling in Rural Mozambique*, Sudhanshu Handa and Kenneth R. Simler, March 2000
- 82 *Pathways of Rural Development in Madagascar: An Empirical Investigation of the Critical Triangle of Environmental Sustainability, Economic Growth, and Poverty Alleviation*, Manfred Zeller, Cécile Lapenu, Bart Minten, Eliane Ralison, Désiré Randrianaivo, and Claude Randrianarisoa, March 2000
- 81 *The Constraints to Good Child Care Practices in Accra: Implications for Programs*, Margaret Armar-Klemesu, Marie T. Ruel, Daniel G. Maxwell, Carol E. Levin, and Saul S. Morris, February 2000
- 80 *Nontraditional Crops and Land Accumulation Among Guatemalan Smallholders: Is the Impact Sustainable?* Calogero Carletto, February 2000
- 79 *Adult Health in the Time of Drought*, John Hoddinott and Bill Kinsey, January 2000
- 78 *Determinants of Poverty in Mozambique: 1996-97*, Gaurav Datt, Kenneth Simler, Sanjukta Mukherjee, and Gabriel Dava, January 2000
- 77 *The Political Economy of Food Subsidy Reform in Egypt*, Tammi Gutner, November 1999.
- 76 *Raising Primary School Enrolment in Developing Countries: The Relative Importance of Supply and Demand*, Sudhanshu Handa, November 1999
- 75 *Determinants of Poverty in Egypt, 1997*, Gaurav Datt and Dean Jolliffe, October 1999
- 74 *Can Cash Transfer Programs Work in Resource-Poor Countries? The Experience in Mozambique*, Jan W. Low, James L. Garrett, and Vitória Ginja, October 1999
- 73 *Social Roles, Human Capital, and the Intrahousehold Division of Labor: Evidence from Pakistan*, Marcel Fafchamps and Agnes R. Quisumbing, October 1999
- 72 *Validity of Rapid Estimates of Household Wealth and Income for Health Surveys in Rural Africa*, Saul S. Morris, Calogero Carletto, John Hoddinott, and Luc J. M. Christiaensen, October 1999
- 71 *Social Capital and Income Generation in South Africa, 1993-98*, John Maluccio, Lawrence Haddad, and Julian May, September 1999
- 70 *Child Health Care Demand in a Developing Country: Unconditional Estimates from the Philippines*, Kelly Hallman, August 1999
- 69 *Supply Response of West African Agricultural Households: Implications of Intrahousehold Preference Heterogeneity*, Lisa C. Smith and Jean-Paul Chavas, July 1999
- 68 *Early Childhood Nutrition and Academic Achievement: A Longitudinal Analysis*, Paul Glewwe, Hanan Jacoby, and Elizabeth King, May 1999
- 67 *Determinants of Household Access to and Participation in Formal and Informal Credit Markets in Malawi*, Aliou Diagne, April 1999
- 66 *Working Women in an Urban Setting: Traders, Vendors, and Food Security in Accra*, Carol E. Levin, Daniel G. Maxwell, Margaret Armar-Klemesu, Marie T. Ruel, Saul S. Morris, and Clement Ahiadeke, April 1999
- 65 *Are Determinants of Rural and Urban Food Security and Nutritional Status Different? Some Insights from Mozambique*, James L. Garrett and Marie T. Ruel, April 1999
- 64 *Some Urban Facts of Life: Implications for Research and Policy*, Marie T. Ruel, Lawrence Haddad, and James L. Garrett, April 1999
- 63 *Are Urban Poverty and Undernutrition Growing? Some Newly Assembled Evidence*, Lawrence Haddad, Marie T. Ruel, and James L. Garrett, April 1999
-

FCND DISCUSSION PAPERS

- 62 *Good Care Practices Can Mitigate the Negative Effects of Poverty and Low Maternal Schooling on Children's Nutritional Status: Evidence from Accra*, Marie T. Ruel, Carol E. Levin, Margaret Armar-Klemesu, Daniel Maxwell, and Saul S. Morris, April 1999
 - 61 *Does Geographic Targeting of Nutrition Interventions Make Sense in Cities? Evidence from Abidjan and Accra*, Saul S. Morris, Carol Levin, Margaret Armar-Klemesu, Daniel Maxwell, and Marie T. Ruel, April 1999
 - 60 *Explaining Child Malnutrition in Developing Countries: A Cross-Country Analysis*, Lisa C. Smith and Lawrence Haddad, April 1999
 - 59 *Placement and Outreach of Group-Based Credit Organizations: The Cases of ASA, BRAC, and PROSHIKA in Bangladesh*, Manohar Sharma and Manfred Zeller, March 1999
 - 58 *Women's Land Rights in the Transition to Individualized Ownership: Implications for the Management of Tree Resources in Western Ghana*, Agnes Quisumbing, Ellen Payongayong, J. B. Aidoo, and Keijiro Otsuka, February 1999
 - 57 *The Structure of Wages During the Economic Transition in Romania*, Emmanuel Skoufias, February 1999
 - 56 *How Does the Human Rights Perspective Help to Shape the Food and Nutrition Policy Research Agenda?*, Lawrence Haddad and Arne Oshaug, February 1999
 - 55 *Efficiency in Intrahousehold Resource Allocation*, Marcel Fafchamps, December 1998
 - 54 *Endogeneity of Schooling in the Wage Function: Evidence from the Rural Philippines*, John Maluccio, November 1998
 - 53 *Agricultural Wages and Food Prices in Egypt: A Governorate-Level Analysis for 1976-1993*, Gaurav Datt and Jennifer Olmsted, November 1998
 - 52 *Testing Nash Bargaining Household Models With Time-Series Data*, John Hoddinott and Christopher Adam, November 1998
 - 51 *Urban Challenges to Food and Nutrition Security: A Review of Food Security, Health, and Caregiving in the Cities*, Marie T. Ruel, James L. Garrett, Saul S. Morris, Daniel Maxwell, Arne Oshaug, Patrice Engle, Purnima Menon, Alison Slack, and Lawrence Haddad, October 1998
 - 50 *Computational Tools for Poverty Measurement and Analysis*, Gaurav Datt, October 1998
 - 49 *A Profile of Poverty in Egypt: 1997*, Gaurav Datt, Dean Jolliffe, and Manohar Sharma, August 1998.
 - 48 *Human Capital, Productivity, and Labor Allocation in Rural Pakistan*, Marcel Fafchamps and Agnes R. Quisumbing, July 1998
 - 47 *Poverty in India and Indian States: An Update*, Gaurav Datt, July 1998
 - 46 *Impact of Access to Credit on Income and Food Security in Malawi*, Aliou Diagne, July 1998
 - 45 *Does Urban Agriculture Help Prevent Malnutrition? Evidence from Kampala*, Daniel Maxwell, Carol Levin, and Joanne Csete, June 1998
 - 44 *Can FAO's Measure of Chronic Undernourishment Be Strengthened?*, Lisa C. Smith, with a Response by Logan Naiken, May 1998
 - 43 *How Reliable Are Group Informant Ratings? A Test of Food Security Rating in Honduras*, Gilles Bergeron, Saul Sutkover Morris, and Juan Manuel Medina Banegas, April 1998
 - 42 *Farm Productivity and Rural Poverty in India*, Gaurav Datt and Martin Ravallion, March 1998
 - 41 *The Political Economy of Urban Food Security in Sub-Saharan Africa*, Dan Maxwell, February 1998
 - 40 *Can Qualitative and Quantitative Methods Serve Complementary Purposes for Policy Research? Evidence from Accra*, Dan Maxwell, January 1998
 - 39 *Whose Education Matters in the Determination of Household Income: Evidence from a Developing Country*, Dean Jolliffe, November 1997
 - 38 *Systematic Client Consultation in Development: The Case of Food Policy Research in Ghana, India, Kenya, and Mali*, Suresh Chandra Babu, Lynn R. Brown, and Bonnie McClafferty, November 1997
-

FCND DISCUSSION PAPERS

- 37 *Why Do Migrants Remit? An Analysis for the Dominican Sierra*, Bénédicte de la Brière, Alain de Janvry, Sylvie Lambert, and Elisabeth Sadoulet, October 1997
 - 36 *The GAPVU Cash Transfer Program in Mozambique: An assessment*, Gaurav Datt, Ellen Payongayong, James L. Garrett, and Marie Ruel, October 1997
 - 35 *Market Access by Smallholder Farmers in Malawi: Implications for Technology Adoption, Agricultural Productivity, and Crop Income*, Manfred Zeller, Aliou Diagne, and Charles Mataya, September 1997
 - 34 *The Impact of Changes in Common Property Resource Management on Intrahousehold Allocation*, Philip Maggs and John Hoddinott, September 1997
 - 33 *Human Milk—An Invisible Food Resource*, Anne Hatløy and Arne Oshaug, August 1997
 - 32 *The Determinants of Demand for Micronutrients: An Analysis of Rural Households in Bangladesh*, Howarth E. Bouis and Mary Jane G. Novenario-Reese, August 1997
 - 31 *Is There an Intrahousehold 'Flypaper Effect'? Evidence from a School Feeding Program*, Hanan Jacoby, August 1997
 - 30 *Plant Breeding: A Long-Term Strategy for the Control of Zinc Deficiency in Vulnerable Populations*, Marie T. Ruel and Howarth E. Bouis, July 1997
 - 29 *Gender, Property Rights, and Natural Resources*, Ruth Meinzen-Dick, Lynn R. Brown, Hilary Sims Feldstein, and Agnes R. Quisumbing, May 1997
 - 28 *Developing a Research and Action Agenda for Examining Urbanization and Caregiving: Examples from Southern and Eastern Africa*, Patrice L. Engle, Purnima Menon, James L. Garrett, and Alison Slack, April 1997
 - 27 *"Bargaining" and Gender Relations: Within and Beyond the Household*, Bina Agarwal, March 1997
 - 26 *Why Have Some Indian States Performed Better Than Others at Reducing Rural Poverty?*, Gaurav Datt and Martin Ravallion, March 1997
 - 25 *Water, Health, and Income: A Review*, John Hoddinott, February 1997
 - 24 *Child Care Practices Associated with Positive and Negative Nutritional Outcomes for Children in Bangladesh: A Descriptive Analysis*, Shubh K. Kumar Range, Ruchira Naved, and Saroj Bhattarai, February 1997
 - 23 *Better Rich, or Better There? Grandparent Wealth, Coresidence, and Intrahousehold Allocation*, Agnes R. Quisumbing, January 1997
 - 22 *Alternative Approaches to Locating the Food Insecure: Qualitative and Quantitative Evidence from South India*, Kimberly Chung, Lawrence Haddad, Jayashree Ramakrishna, and Frank Riely, January 1997
 - 21 *Livestock Income, Male/Female Animals, and Inequality in Rural Pakistan*, Richard H. Adams, Jr., November 1996
 - 20 *Macroeconomic Crises and Poverty Monitoring: A Case Study for India*, Gaurav Datt and Martin Ravallion, November 1996
 - 19 *Food Security and Nutrition Implications of Intrahousehold Bias: A Review of Literature*, Lawrence Haddad, Christine Peña, Chizuru Nishida, Agnes Quisumbing, and Alison Slack, September 1996
 - 18 *Care and Nutrition: Concepts and Measurement*, Patrice L. Engle, Purnima Menon, and Lawrence Haddad, August 1996
 - 17 *Remittances, Income Distribution, and Rural Asset Accumulation*, Richard H. Adams, Jr., August 1996
 - 16 *How Can Safety Nets Do More with Less? General Issues with Some Evidence from Southern Africa*, Lawrence Haddad and Manfred Zeller, July 1996
 - 15 *Repayment Performance in Group-Based credit Programs in Bangladesh: An Empirical Analysis*, Manohar Sharma and Manfred Zeller, July 1996
 - 14 *Demand for High-Value Secondary Crops in Developing Countries: The Case of Potatoes in Bangladesh and Pakistan*, Howarth E. Bouis and Gregory Scott, May 1996
-

FCND DISCUSSION PAPERS

- 13 *Determinants of Repayment Performance in Credit Groups: The Role of Program Design, Intra-Group Risk Pooling, and Social Cohesion in Madagascar*, Manfred Zeller, May 1996
 - 12 *Child Development: Vulnerability and Resilience*, Patrice L. Engle, Sarah Castle, and Purnima Menon, April 1996
 - 11 *Rural Financial Policies for Food Security of the Poor: Methodologies for a Multicountry Research Project*, Manfred Zeller, Akhter Ahmed, Suresh Babu, Sumiter Broca, Aliou Diagne, and Manohar Sharma, April 1996
 - 10 *Women's Economic Advancement Through Agricultural Change: A Review of Donor Experience*, Christine Peña, Patrick Webb, and Lawrence Haddad, February 1996
 - 09 *Gender and Poverty: New Evidence from 10 Developing Countries*, Agnes R. Quisumbing, Lawrence Haddad, and Christine Peña, December 1995
 - 08 *Measuring Food Insecurity: The Frequency and Severity of "Coping Strategies,"* Daniel G. Maxwell, December 1995
 - 07 *A Food Demand System Based on Demand for Characteristics: If There Is "Curvature" in the Slutsky Matrix, What Do the Curves Look Like and Why?*, Howarth E. Bouis, December 1995
 - 06 *Gender Differentials in Farm Productivity: Implications for Household Efficiency and Agricultural Policy*, Harold Alderman, John Hoddinott, Lawrence Haddad, and Christopher Udry, August 1995
 - 05 *Gender Differences in Agricultural Productivity: A Survey of Empirical Evidence*, Agnes R. Quisumbing, July 1995
 - 04 *Market Development and Food Demand in Rural China*, Jikun Huang and Scott Rozelle, June 1995
 - 03 *The Extended Family and Intrahousehold Allocation: Inheritance and Investments in Children in the Rural Philippines*, Agnes R. Quisumbing, March 1995
 - 02 *Determinants of Credit Rationing: A Study of Informal Lenders and Formal Credit Groups in Madagascar*, Manfred Zeller, October 1994
 - 01 *Agricultural Technology and Food Policy to Combat Iron Deficiency in Developing Countries*, Howarth E. Bouis, August 1994
-